



Introductions

Participants:

Lynae Craig
Amy Fuller-Lyman
Joseph Galgano
Shelia Ipock
Sarah Kilpatrick

Alice Rademacher

David Pyeatt

Bob Stanford
Ray Stibenski
Nick Straka
Josh Stuckey
Vickie Swain
Andrew Warner
Josie Wilson

Others

Thanks for joining us today!



Kodiak Benny Benson State Airport (ADQ)

- Regional Part 139 hub airport for both public and military use.
- Accommodates the largest operating U.S. Coast Guard (USCG) installation.
- The only base that hosts both aircraft and ships.
- This USCG base responds to emergencies for the entire Kodiak region and Aleutian Islands.



Project Team

Who is performing the work on this project?



DOT&PF is partnering with HDR and their subconsultants, Shannon & Wilson, Inc., MBA Consulting Engineers, Inc., and Lounsbury and Associates, to perform the work for this project.












Project Overview



The Alaska Department of Transportation and Public Facilities (DOT&PF) is proposing maintenance improvements to the Kodiak Airport Facility.


The existing facility has experienced a fair amount of deterioration in recent years as it's asphalt surfaces approach 20 years of age. Because they are reaching the end of their useful life, the existing pavement structures and airfield lighting are to be replaced.

The project is a conglomerate of three Notices to Proceed (NTP)


Each NTP will represent a separate construction season.

- •NTP 1 (2022) will include work occurring around the Apron, Taxiway (TW) F, and General Aviation surfaces.
- •NTP 2 (2023) will include work occurring around TW C and TW D.
- •NTP 3 (2024) will include work occurring around Runway (RW) 11-29 and TW E.

Summary of Work: NTP 1 Design




Visualization Proposed - Apron





Summary of Work: NTP 2 Design



- Conduct heave repair on Taxiway C and Runway 1/19.
- Relocate service road that parallels **Taxiways C and D** to outside the ADG III taxiway object-free area (TOFA) and ADG IV taxiway safety area (TSA).
- Pave service road driveways onto Taxiways C, D, and F.
- Remove existing connector **Taxiway D** pavement and reestablish infield grassy areas.
- Replace existing storm infrastructure and pipes. Regrade infield areas to Federal Aviation Administration standards.
- Replace associated edge lights, home runs, transformers, and signs.
- Relocate TW C fire hydrant to service road.
- Clear trees and brush that block the Tower's view of TW B and TW C.

CSPP

- Sub-Phasing is shown in the image above.
- What are acceptable durations for each sub-phase?
- How long (in days) can RW 1-19 be closed to replace the storm drain crossing?
- When is the best time of day to close RW 8-26 and RW 1-19 for work inside the RSA?



Visualization Proposed – Taxiway D






Visualization Proposed – Taxiway C





Summary of Work: NTP 3 Design



- Resurface Runway 11/29 and Taxiway E with a crowned grade.
- Conduct heave repair on Runway 11/29 and Taxiway E.
- Pave service road driveways to Runway 11/29 and Taxiway E.
- Replace associated edge lights, home runs, transformers, and signs.
- Replace existing storm infrastructure and regrade infield areas to Federal Aviation Administration standards.
- Reconstruct RW 11 bulb and intersecting TW E which will require removal of underlying concrete to facilitate intersection grading.
- Repair damage at the end of RW 8.

CSPP

- Sub-Phasing is shown in the image above.
- What are acceptable durations for each sub-phase?
- When is the best time of day to close RW 8-26 and RW 1-19 for work inside the RSA?



Visualization Proposed – Runway 11-29





Visualization Proposed – RW 11-29 and Taxiway E





Project Funding

- The project cost will be approximately \$45,000,000.
- Approximately 95% of this project cost will be funded by the Federal Aviation Administration
- The remaining balance will be paid by the State of Alaska.





Environmental Processes

Development of this proposed project would follow a process required by the National Environmental Policy Act (NEPA).

Based on project location and scope of work, the required NEPA environmental document is anticipated to be a Focused EA.



Possible Affected Resources

- Hazardous Waste
- Historic Properties
- Section 4f/6f Properties
- Fish




Project Status & Schedule

The project design is currently 65% complete.

Next Steps:

- Receive public feedback and comment
- Further the design plan to 100%
- Plan and follow all NEPA requirements
- Construction anticipated for NTP 1 is 2022, NTP 2 is 2023, and NTP 3 is 2024






Additional Resources

Visit the Project Website for Additional Details:

http://www.kodiakairportrehab.com/



Project Contacts

Project Manager

David Pyeatt, P.E.

DOT&PF Project Manager

Phone: (907) 465-4490

Email: david.pyeatt@alaska.gov

Environmental Contact

Joseph Galgano
DOT&PF Environmental Impact Analyst

Phone: (907) 465-4447

Fax: (907) 465-4414

Email: joseph.galgano@alaska.gov

Engineering Contact

Nick Straka, HDR Project Manager HDR

Phone: (907) 644-2032

Email: <u>nick.straka@hdrinc.com</u>

Public Outreach Contact

Josie Wilson, HDR Strategic Communications HDR

Phone: (907) 644-2030

Email: Josie.Wilson@hdrinc.com



